

Subdivisions of T. 1 N., R. 34 E.

Chains	
70.00	Top of sharp ridge.
75.00	Canyon, course S.W.
80.00	Set a basalt stone, 12x10x8 ins., 8 ins. in the ground, for cor. to secs. 25, 26, 35 and 36, marked one notch on S. and one notch on E. edges and raised a mound of stone over it.
	Land, very rough and mountainous with bunch grass. 80 chs. Some pine and fir timber on McKay Creek.
	Soil, 4th rate.
	East on random between 25 and 36.
	Var. 19°30'E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.16	Intersect E. bdy., 14 lks. N. of cor. to secs. 25, 30, 31 and 36. Thence I run N.89°54'W. on true line.
10.00	Top of mountain.
12.00	Enter level prairie.
28.00	Low Swag.
40.08	Set stone, 10x8x7 ins., 7 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. side, from which A pine, 10 ins. in diam., bears S.25°W., 200 lks., marked $\frac{1}{4}$ S B T. No other tree in limits. Raised mound of stone over it.
46.00	Enter pine timber.
80.16	To cor. of secs. 25, 26, 35 and 36. Land, undulating with scattering pine timber. Soil, 2nd rate.
	North between secs. 25 and 26.
	Var. 19°30'E.
12.00	Canyon, course W.
21.00	Bluff of rock.
27.00	Top of hill.