

Subdivisions of T. 1 N., R. 34 E.

| | |
|--------|--|
| Chains | <p>A fir, 16 ins. diam., bears N.85°W., dist. 45 lks., marked $\frac{1}{4}$ S B T.</p> <p>Erected mound of stone over it.</p> |
| 65.00 | Gulch, course N. |
| 80.25 | To cor. of secs. 11, 12, 13 and 14. |
| | Land, rough and mountainous. 80.25 chs. |
| | Some timber on N. hillsides. |
| | Soil, rocky, 4th rate. |
| | North between secs. 11 and 12. |
| | Var. 27° E. |
| 10.25 | A creek, 6 lks. wide, course W. |
| 32.50 | Summit of ridge, S.W. |
| 40.00 | Set basalt stone, 12x10x8 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor. I raised mound of stone over it. |
| 61.50 | Canyon and creek, 2 lks. wide, course S.W. |
| 80.00 | Set basalt stone, 30x20x20 ins., 20 ins. in the ground, 5 notches on S., 1 notch on E. edges, for cor. to secs. 1, 2, 11 and 12. Erected a mound of stone over it. |
| | Land, mountainous. 80 chs. |
| | Scattering pine timber in canyons. Good grass. |
| | Soil, rocky, 2nd rate. |
| | East on random between secs. 1 and 12. |
| | Var. 17° E. |
| 40.00 | Set temporary $\frac{1}{4}$ sec. cor. |
| 80.05 | Intersect T. line, 63 lks. S. of cor. Thence I run S.89°33'W. on true line. |
| 15.50 | Gulch, course S.W. |
| 33.00 | Top hill. |
| 40.02 | Set a basalt stone, 12x10x6 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor., raised mound of stone over it. Pits impracticable. |
| 69.00 | Canyon, water in holes, course S.W. |
| 80.05 | To cor. to secs. 1, 2, 11 and 12. |