

## Subdivisions of T. 1 N., R. 34 E.

Chains	East on random between secs. 23 and 26. Var. 18°45'E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect E. boundary at cor. to secs. 23, 24, 25 and 26. Thence I run W. on true line.
30.00	Begin to descend.
34.50	Gulch, course N.W.
40.00	Set basalt stone, 12x10x6 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor., from which A pine, 4 ins. in diam., bears S.20°W., dist. 15 lks., marked $\frac{1}{4}$ S B T. A fir, 12 ins. in diam., bears N.5°W., dist. 50 lks., marked $\frac{1}{4}$ S B T.
45.00	Gulch, course N.
80.00	To cor. to secs. 22, 23, 26 and 27. Land, broken and mountainous. 80 chs. Scattering pine timber. Good bunch grass. Soil, 3rd rate.
	North between secs. 22 and 23. Var. 18°45'E.
18.50	Gulch, course W.
40.00	Set basalt stone, 16x8x8 ins., 11 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor. Raised mound of stone over it. Pits impracticable.
60.00	Gulch, course W.
80.00	Set basalt stone, 18x9x9 ins., 14 ins. in the ground, marked 3 notches on S. and 2 notches on E. edges, for cor. to secs. 14, 15, 22 and 23. Raised mound of stone over it. Pits impracticable. Land, rough and mountainous. 80.00 chs. Soil, 3rd rate.
	East on random between secs. 14 and 23. Var. 24°E.