

## Subdivisions of T. 1 N., R. 34 E.

Chains	East on random between secs. 2 and 11. Var. 19°45' East.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.05	Intersect N. and S. line, 63 lks. S. of cor. to secs. 1, 2, 11 and 12. Thence I run S.89°33'W. on true line.
3.00	Top of mountain.
26.50	Canyon, course S.W.
40.02	Set post, 3 ft. long, 3 ins. square, 24 ins. in the ground, marked $\frac{1}{4}$ S on N. face, for $\frac{1}{4}$ sec. cor., from which A pine, 18 ins. diam., bears S.50°E., dist. 10 lks., marked $\frac{1}{4}$ S B T. A pine, 16 ins. diam., bears N.10°W., dist. 77 lks., marked $\frac{1}{4}$ S B T.
56.00	Gulch, course N.
67.00	Gulch, course S.W.
75.00	Top ridge, course S.
77.00	Canyon, course S.E.
80.05	To cor. secs. 2, 3, 10 and 11. Land, mountainous. 80.05 chs. Scattering pine timber. Good bunch grass. Soil, 3rd rate.
	North on random between secs. 2 and 3. Var. 19°45' E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.87	Intersect T. line, 22 lks. W. of cor. to secs. 2, 3, 34 and 35. Thence I run S.9°W. on true line.
26.75	Pendleton and LaGrande wagon road.
40.87	Set basalt stone, 12x12x12 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor. Raised mound of stone over it. Pits impracticable.
77.50	Gulch, course S.E.