

Subdivisions of T. 1 N., R. 34 E.

Chains 80.87	To cor. secs. 2, 3, 10 and 11. Land, broken and mountainous. 80.87 chs. Good bunch grass. Soil, 3rd rate.
	From cor. to secs. 33 and 34 on S. bdy. of Township I run North between secs. 33 and 34. Var. 20°15'E.
8.00	Summit of hill.
26.00	Canyon, course W.
40.00	Set basalt stone, 18x12x10 ins., 14 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor., raised mound of stone over it. Pits impracticable.
80.00	Set a post, 4 ft. long, 4 ins. sq., 2ft. in ground, marked T 1 N R 34 E S 27 on N.E., S 28 N.W., S 33 S.W., S 34 S.E. One notch on S. and 3 notches on E. edges, for cor. to secs. 27, 28, 33 and 34, from which A pine, 18 ins. diam., bears N.85°W., dist. 72 lks., marked T 1 N R 34 E S 28 B T. A pine, 12 ins. diam., bears S.60°W., dist. 70 lks., marked S 33 B T. A pine, 20 ins. diam., bears N.82°E., dist. 228 lks., marked Sec. 27 B T. No other tree in limits. Land, mountainous, 80.00 chs., covered with scattering pine timber and bunch grass. Soil, 3rd rate.
	East on random between secs. 27 and 34. Var. 22° E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.07	Intersect N. and S. line, 7 lks. N. of cor. to secs. 26, 27, 34 and 35. Thence I run N.89°57'W. on true line.
36.66	Gulch, course S.