

Subdivisions of T. 1 N., R. 34 E.

Chains 39.75	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground, marked $\frac{1}{4}$ S on N. face, from which</p> <p>A pine, 28 ins. diam., bears S.60°W., dist. 54 lks., marked $\frac{1}{4}$ S B T.</p> <p>A pine, 30 ins. diam., bears S.30°E., dist. 109 lks., marked $\frac{1}{4}$ S B T.</p>
40.25	Bluff.
62.50	Top of ridge.
75.00	Canyon.
79.50	To cor. secs. 21, 22, 27 and 28.
	Land, mountainous. 79.50 chs.
	Scattering Pine timber along creek. Good bunch grass.
	Soil, 3rd rate.
	North between secs. 21 and 22.
	Var. 22°E.
	Ascend mountain.
32.50	Summit, course N.E.
40.00	Set basalt stone, 18x8x6 ins., 14 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor., raised mound of stone over it. Pits impracticable.
43.75	Gulch, course N.W.
69.00	Summit of ridge.
80.00	Set basalt stone, 12x10x6 ins., 18 ins. in the ground, marked 3 notches on S., 3 notches on E. edges, for cor. to secs. 15, 16, 21 and 22. Raised mound of stone over it. Pits impracticable.
	Land, rough and mountainous. 80 chs.
	Pine and fir timber on N. hillsides.
	Soil, rocky, 3rd rate.
	East on random between secs. 15 and 22.
	Var. 19°25'E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.40	Intersect N. and S. line, 30 lks. S. of cor. to secs. 14, 15, 22 and 23. Thence I run