

Subdivisions of T. 1 N., R. 34 E.

| | |
|-----------------|--|
| Chains 35.00 | Canyon, course S. |
| 39.92 | Set basalt stone, 14x10x6 ins., 9 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor., raised mound of stone over it. Pits impracticable. |
| 49.00 | Top of mountain. |
| 79.84 | To cor. to secs. 9, 10, 15 and 16. Land, rough and mountainous. 79.84 chs. Pine and fir timber in canyons. Soil, 3rd rate. August 6, 1887. |
| | North between secs. 9 and 10. Var. $21^{\circ}45'E$. |
| 10.00 | Canyon, course S.W. |
| 40.00 | Set post, 3 ft. long, 3 ins. sq., 2 ft. in ground, marked $\frac{1}{4}$ S on N. face, for $\frac{1}{4}$ sec. cor., from which A pine, 18 ins. diam., bears $S.75^{\circ}W.$, dist. 78 lks., marked $\frac{1}{4}$ S B T. A pine, 18 ins. diam., bears $N.57^{\circ}E.$, dist. 66 lks., marked $\frac{1}{4}$ S B T. |
| 80.00 | Set basalt stone, 12x10x8 ins., 8 ins. in the ground, marked 5 notches on S., and 3 notches on E. edges, raised mound of stone over it, for cor. to secs. 3, 4, 9 and 10. Pits impracticable. Land, mountainous. 80.00 chs. Good pine timber on $S.\frac{1}{2}$. Soil, 3rd rate. |
| | East on random between secs. 3 and 10. Var. $21^{\circ} E$. |
| 40.00 | Set temporary $\frac{1}{4}$ sec. cor. |
| 80.25 | Intersect N. and S. line at cor. to secs. 2, 3, 10 and 11. Thence I run W. on true line. |
| 15.00 | Summit of ridge, course S. |
| 29.50 | Gulch, course S. |
| 40.12 | Set basalt stone, 12x12x12 ins., 8 ins. in the ground, |