

## Subdivisions of T. 1 N., R. 34 E.

|        |  |
|--------|--|
| Chains | over it. Pits impracticable.   |
| 70.00  | Top of ridge, course W.  |
| 80.00  | Set basalt stone, 14x12x10 ins., 9 ins. in the ground, marked 1 notch on S. and 4 notches on E. edges, for cor. to secs. 28, 29, 32 and 33, from which.<br>A pine, 8 ins. diam., bears N.35°W., dist. 87 lks., marked S 29 T 1 N B T.<br>A pine, 6 ins. diam., bears S.29°E., dist. 100 lks., marked R 34 E S 33 B T.<br>A pine, 6 ins. diam., bears S.26°W., dist. 64 lks., marked S 32 B T.<br>No other tree in limit.<br>Land, mountainous. 80.00 chs.<br>Soil, 3rd rate. |
|        | East on random between secs. 28 and 33.<br>Var. 19°30'E.   |
| 40.00  | Set temporary $\frac{1}{4}$ sec. cor.  |
| 80.15  | Intersect N. and S. line at cor. Thence I run W. on true line.   |
| 30.00  | Top of ridge, course North.  |
| 40.07  | A basalt stone, 4x3x2 ft., in place which I marked for $\frac{1}{4}$ sec. cor. with $\frac{1}{4}$ on N. face and a cross (x) at exact corner point, raised a mound of stone alongside. Pits impracticable.   |
| 54.50  | Canyon, course N.  |
| 60.00  | Top of ridge, course N.  |
| 80.15  | To cor. to secs. 28, 29, 32 and 33.<br>Land, mountainous and rough. 80.15 chs.<br>Some bunch grass.<br>Soil, rocky, 3rd rate.  |
|        | North between secs. 28 and 29.<br>Var. 19°30'E.  |
| 00.75  | Gulch, water in holes.   |
| 5.00   | Top of ridge, course N.E.  |