

Subdivisions of T. 1 N., R. 34 E.

Chains	<p>Land, rough and mountainous. 81.06 chs. Good grass. Soil, 3rd rate.</p>
	<p>From the cor. to secs. 31 and 32 on South bdy. of Township I run North between secs. 31 and 32. Var. 18°30'E.</p>
38.50	A fork McKay Creek, 40 lks. wide, course S.W.
40.00	Set boulder, 18x10x8 ins., 14 ins. in the ground, on a gravel border, 40 lks. W. of true position, for a witness cor. to $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ W C on W. face. Raised a mound of stone over it.
46.00	Bluff.
69.25	Spring branch, 5 lks. wide, course S.E.
80.00	Set basalt stone, 15x12x10 ins., for cor. to secs. 29, 30, 31 and 32, marked 1 notch on S. edge and 5 on E. edge. Raised a mound of stone over it. Pits impracticable. Stone 10 ins. in the ground.
	<p>Land, mountainous and steep. 40 chs. Scattering pine timber in canyons. Soil, 3rd rate.</p>
	<p>East on random between secs. 29 and 32. Var. 22° E.</p>
40.06	Set temporary $\frac{1}{4}$ sec. cor.
80.12	Intersect N. and S. line, 36 lks. S. of cor. to secs. 28, 29, 32 and 33. Thence I run S.89°45'W. on true line.
4.00	Top of ridge, course N.W.
10.00	McKay Creek, 20 lks. wide, course S.W.
20.25	Leave Creek bottom.
40.06	Set post, 3 ft. long by 3 ins. sq., 24 ins. in ground, marked $\frac{1}{4}$ S on N. face, for $\frac{1}{4}$ sec. cor., from which A pine, 16 ins. in daim., bears N.10°E., dist. 264 lks., marked $\frac{1}{4}$ S B T; also