

Subdivisions of T. 1 N., R. 34 E.

Chains	S. 54° W. on true line.
31.25	Pendleton and LaGrande road on summit, bears N.W.
40.25	Set basalt stone, 16x12x12 ins., 12 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.
52.50	Canyon, course W.
80.25	To cor. to secs. 5, 6, 7 and 8. Land, rolling and covered with good bunch grass. Soil, 2nd rate.
	August 10, 1887.
General Description	
This Township is mountainous and broken. There are some fine bodies of pine and fir timber. It is well watered and covered with good bunch grass. The soil is rocky, 4th rate.	
Topography of T. 1 N., R. 34 E. Surveyed by Currin and Noland under special contract. Dated May 4, 1887.	
Line between secs. 3 and 4. From cor. secs. 3, 4, 9 and 10, which is a stone, 12x10x8, firmly set in the ground with 3 notches on E. and 5 on South edges.	
North between secs. 3 and 4. Var. 21° E.	
25.90	Pendleton and LaGrande Road, course W. April 27, 1890.
Subdivisions and Allotments of T. 1 N., R. 34 E. Surveyed by James P. Currin under contract No. 537. Dated March 5, 1889.	
Sec. 5	
From the corner to secs. 4, 5, 8 and 9, which is a basalt stone, 10x8x8 ins., 7 ins. in the ground, marked with 5 notches on S. and 4 notches on E. edges, and mound of	