

Subdivisions and Allotments of T. 1 N., R. 34 E.

Chains	Sec. 5
	Thence I run S.89° 47' West on true line through the S. $\frac{1}{2}$ of sec. 5. Var. 20° E.
1.50	Summit, N.E.
20.00	Set basalt stone, 10x10x8 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x 18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
40.00	Set basalt stone, 10x8x7, 7 ins. in the ground for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
41.50	Gulch, course N.
55.00	Road, from La Grande to Pendleton, course N.
60.00	Set basalt stone, 14x8x6 ins., 10 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face, and raised mound of stone alongside. Pits impracticable.
65.00	Gulch, course N.80° W.
75.00	" " N.
80.00	" " "
	To the 1/16 sec. corner, 20 chs. N. of corner to secs. 5, 6, 7 and 8. Land, rolling, mountainous. Soil, 1st rate. Covered with good grass and sunflower.
	From the 1/16 sec. corner, 20 chains N., and 20 chs. E. of cor. to secs. 5, 6, 7 and 8. I run North on a true line in sec. 5. Var. 21° East.
8.00	Pendleton and La Grande Wagon Road, course S.E.
20.00	Set basalt stone, 10x9x8 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face, and raised a mound of stone over it. Pits impracticable.