

Subdivisions and Allotments of T. 1 N., R. 34 E.

Chains	Sec. 8
	<p>From the 1/16 sec. corner, 20 chs. West of corner to secs. 4, 5, 8 and 9.</p> <p>I run South on true line in section 8.</p> <p style="text-align: center;">Var. 21°E.</p>
16.00	Road, course W.
20.00	<p>Set stone, 14x9x7 ins., 10 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face, and raised a mound of stone over it. Pits impracticable.</p> <p>Land, rolling with some rocky flats on summit of Mt.</p> <p>Soil, generally 1st rate.</p> <p>Good grass and sunflower.</p>
	<p>From the 1/16 sec. corner, 20 chs. S. and 20 chs. E. of corner to secs. 5, 6, 7 and 8.</p> <p>I run East on random line in sec. 8.</p> <p style="text-align: center;">Var. 21°E.</p> <p>Setting temporary corner at 20 chs., and at</p>
39.90	<p>Intersect 1/16 sec. corner, 20 chains E. and 20 chs. S. of corner to secs. 4, 5, 8 and 9.</p> <p>Thence I run West on true line in sec. 8.</p> <p style="text-align: center;">Var. 20°30'E.</p>
19.95	<p>Set stone, 12x9x8 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face and raised a mound of stone over it.</p>
30.00	Road, course S. and W.
39.90	<p>To 1/16 section corner in section 8, 20 chs. S., and 20 chs. E. of corner to secs. 5, 6, 7 and 8.</p> <p>Land, gently rolling.</p> <p>Soil, 1st rate and rocky.</p> <p>Good grass.</p>
	<p>From the corner to secs. 7, 8, 17 and 18, which is a basalt stone, 12x10x8 ins., 8 ins. in the ground,</p>