

## Subdivisions and Allotments of T. 1 N., R. 34 E.

Chains	Sec. 8
	Thence I run West on true line in sec. 8. Var. 19° E.
20.00	Set basalt stone, 12x9x7 ins., .8 ins. in the ground, for 1/16 and 1/32 sec. corner marked 1/16 on S., 1/32 on N. faces, and raised a stone mound over it. Pits impracticable.
21.00	Gulch, course N.W.
30.00	To the 1/32 sec. corner, 10 chs. E. and 20 chs. N. of corner to secs. 7, 8, 17 and 18. Land, rolling. Soil, 1st rate. Scattering pine timber and grass.
	From the 1/16 and 1/32 sec. corner, 20 chs. E., and 20 chs. N. of the corner to secs. 7, 8, 17 and 18. I run North on a true line in sec. 8. Var. 21° E.
8.50	Gulch, course W.
10.00	Stone in place, 12x12x8 ins., above ground, for 1/32 sec. corner marked 1/32 on W. face and (*) cross at exact corner, and raised a mound of stone over it. Pits impracticable. Land, rolling. Soil, 1st rate. Scattering pine timber, and grass.
	June 29, 1889.
	<b>General Description</b> The lands allotted in this Township are situated on and near summit of Blue Mts., and are rolling and broken. Soil mostly 1st rate, producing grass, sunflower and some pine timber.