

T. 1 N., R. 35 East

Chains		
	A Spruce 12 inches in diam. bears S25°E. 27 lks. dist.	
	A Spruce 10 " " " " N3°E. 28 lks. dist.	
51.25	Bottom of slope, small ditch of water.	-5
80.00	Set post corner to Secs. 33 & 34, from which	
	A Spruce 12 ins. in diam. bears SW 3 lks. dist.	
	A Red Fir 16 " " " " N60° East.	
	A Spruce 16 " " " " N30°W 28 lks. dist.	
	Var. 21°30' East.	
	In this mile there is much burnt timber, thick young groves of spruce, tamarack and fir. Abundant growth of fine green grass.	
<hr/>		
	Thence East on South boundary of Sec. 34.	
	Var. 21°30' East.	
36.50	A Branch 25 lks. wide runs N.E., water in holes.	-25
40.00	Set qr. sec. post, from which	
	A Spruce 10 ins. in diam. bears N30°W 52 lks. dist.	+10
	A " 7 " " " " S20°E 45 " "	
40.60	Old Emigrant Road, course N40° W.	
77.00	Bottom of hollow.	-100
80.00	Set post corner to secs. 34 & 35, from which	
	A Spruce 12 ins. in diam. bears N.70°W 42 lks. dist.	
	" " 12 " " " " N5°E 43 " "	
	" " 14 " " " " S.E. 51 " "	
	Var. 18°30' E.	
	Excellent grass on the bottom.	
	Timber, etc., as in the previous mile.	
<hr/>		
	East on South boundary of Sec. 35.	
	Var. 18°30' East.	
9.84	A Pine 30 ins. in diam.	+100
40.00	Set qr. sec. post, from which	-200
	A Spruce 8 ins. in diam. bears N70°E 40 lks. dist.	
	" " 8 " " " " S40°E 20 " "	
46.00	Bottom of ravine, touch creek 20 lks. wide, runs East.	-200