

T. 1 N., R. 35 East

Chains		
	Water in holes.	
58.50	Top of ridge.	+500
67.20	A Branch 15 lks. wide runs North.	-400
80.00	Set post corner to Secs. 35 & 36, from which	+400
	A Tamarack, 12 ins. in diam. bears S.25°W 18 lks. dist.	
	A Pine 12 " " " " N.50°W. 36 lks. "	
	A Tamarack 12 " " " " N60°E., 7 " "	
	Variation 20°45' East.	
	Surface of this mile is badly broken, but little room for soil. Timber as before.	
<hr/>		
	Thence East on South boundary of Sec. 36.	
	Var. 20°45' East.	
15.00	Commence to descend.	
32.50	Bottom of ravine. Dry branch, 10 lks. wide, runs North.	-600
40.00	Set qr. sec. post on the side of ridge and from which	+400
	A Pine 36 ins. in dia. bears S70°E., 48 lks. dist.	
	" " 14 " " " " S35 E. 112 lks. dist.	
47.00	Top of table.	+200
80.00	Set post corner to secs. 31 & 36, Township 1, North, Ranges 35 & 36 East, from which	
	A Spruce, 8 ins. in diam. bears N60°E 31 lks. dist.	
	A Pine 14 " " " " N15°W 37 " "	
	" " 12 " " " " S50°W 32 " "	
	Var. 20°30' E.	
	Surface of last half mile slightly uneven. Soil and timber as before.	
	August 9th, 1863.	
<hr/>		
	Field Notes of the Survey of the East boundary of T. 1, N., R. 35 E., by Z. F. Moody, under his contract No. 145, dated Apr. 23, 1871.	
<hr/>		
	From the South East corner of Township 1 North, Range 35 East, I run	
	North on East boundary of Sec. 36.	
	Var. 20° East.	