

E. bdry. T. 1, N., R. 35 East.

Chains		
	North on East boundary of Sec. 13.	
	Var. 21° East.	
40.00	Set post for $\frac{1}{4}$ Sec. corner, from which A Pine, 20 ins. in diam. bears S30°W. 50 lks.	
74.50	Brook, 6 lks. wide, flows W.	-450
80.00	Set post and made stone mound for corner to Secs. 12, 13, 7, 18.	+200
	Land, mountainous. Soil, 2nd rate. Pine and fir timber.	
<hr/>		
	North on East boundary of Sec. 12.	
	Var. 21°30' East.	
40.00	Set basalt stone, 14x14x12, for $\frac{1}{4}$ Sec. corner.	+ 150
80.00	Set basalt stone, 18x18x14 for corner to secs. 1, 12, 6, 7.	+ 100
	Land, mountainous. Soil, 2nd rate. Some good grass.	
<hr/>		
	North on East boundary of Sec. 1.	
	Var. 21°30' East.	
40.00	Set post for $\frac{1}{4}$ Sec. corner, from which A Pine, 38 ins. in diam. bears S10°W. 175 lks.	
80.00	Set post for corner to Townships 1 & 2, North, Ranges 35 and 36 East Willamette Meridian, from which A Fir 20 ins. in diam. bears S80°W., 30 lks. " " 18 " " " " N10°W., 20 "	
	Land, mountainous. Soil, 2nd rate. Some grass. But little timber on this line.	
	May 15th, 1871.	
<hr/>		
	North Boundary T. 1, N., R. 35 E.	
<hr/>		
	West on random line on North Boundaries of Secs. 1, 2, 3, 4, 5, 6.	
	Var. 21°30' East.	
	I set temporary half mile and mile posts and at 5 miles 78 chains and 75 links to a point 2 chains and 30	