

T. 1 N., R. 35 East.

Chains		
26.60	Begin to descend.	
40.00	Set a basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone alongside. Pits impracticable.	-100
65.51	Descend bluff of rock 20 ft. high.	
77.10	Branch, 5 lks. wide. Course N.W.	-140
80.00	To a tamarack 4 ins. in diam., which I marked for cor. to secs. 1, 2, 35 & 36. T2,N.R.35 E. S.35 on N.W. S.36 on N.E. T.1N.R. 35E. S.2 on S.W. S.1 on S.E. 1 notch on E. & 5 on W. edges. Raised a mound of stone alongside of tree. Pits impracticable.	
	Land, mountainous 80. chs.	
	Soil, rocky, 4th rate.	
	Scattering pine and tamarack in canyon. Bunch grass.	
	<hr/>	
	South 89° 48' W on S. bdy. Sec. 35.	
		Var. 25° East.
18.60	Small Spruce grove.	
40.00	Set a basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised a mound of stone alongside. Pits impracticable.	
40.60	Top of ridge. Course N.W.	+1200
50.60	Bluff of rock. Descend.	
79.85	Creek, 15 lks. wide. Course N.W.	-1200
80.00	Set a basalt stone 12 x 10 x 6 ins., 8 ins. in the ground for cor. to secs. 2,3,34 & 35. Marked 2 notches on E. & 4 on W. edges. Raised md. of stone alongside. Pits impracticable.	
	Land, mountainous 80. chs.	
	Soil, all rock, 8th rate; unfit for anything.	
	No timber or grass.	
	<hr/>	
	South 89° 48' W. on S. bdry. S. 34.	
		Var. 27° 15' East
11.00	Timbered canyon.	-60