

Base Line, T. 1 N.R. 35 E. (So. boundary)

Chains	
	<p>S.C. $\frac{1}{4}$S on N. face, from which</p> <p>A Black Pine, 12 ins. in diam. (old B.T.) bears N.3°E. 28 lks dist., marked $\frac{1}{4}$ S.S.C.B.T.</p> <p>A Black Pine, 16 ins. in diam. (old B.T.) bears S.25°E. 27 lks. dist., marked $\frac{1}{4}$S.S.C.B.T.</p>
51.60	Creek, 10 lks. wide, runs S.
76.00	Pendleton and LaGrande wagon road, course N. and S.
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground in exact place of old corner for cor. to secs. 33 and 34, marked S.C.T.1N.R.35E. on N.; S34 on E. and S.33 on W. faces, with 3 notches on E. and W. edges, from which</p> <p>A Fir, 10 ins. in diam. bears N40°E 46 lks., marked S.C.T.1N.R.35 E. S34 B.T.</p> <p>A Hemlock, 18 ins. in diam. bears S40°E 19 lks. dist., marked S.C.T.1 S. R.35 E. B.T.</p> <p>A Hemlock, 8 ins. in diam. bears N85°W. 68 lks. dist., marked S.C.T.1 N.R.35 E. S.33 B.T.</p> <p>The old bearing trees at this cor. are all dead and some of them are fallen.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p> <p>Dense undergrowth of: Spruce, Pine, Hemlock & Fir 80 chs.</p> <p>Timber: Same.</p> <p>Good grass.</p>
	<p>East on S. bdy. of Sec. 34, retracing old line.</p> <p style="text-align: right;">Var. 19° East.</p>
36.55	Creek, 20 lks, course S.
40.00	<p>Set basalt stone 16 x 12 x 9 ins., 10 ins. in the ground at exact place of old cor. for $\frac{1}{4}$ sec. cor., marked S.C. $\frac{1}{4}$ on N. face, from which</p> <p>A Pine, 12 ins. in diam. (old B.T.) bears S.20°E. 45 lks. dist., marked S.C. $\frac{1}{4}$ S.B.T.</p> <p>A Pine, 10 ins. in diam. bears N.26°E. 54 lks. dist.,</p>