

Base Line, T. 1 N. R., 35 E. (So. boundary)

Chains		
48.00	Perpendicular Bluff, 50 ft. high. Ascend.	
58.00	Top of ridge.	+600
67.50	Sheep Creek, 15 lks. course N. Ascend.	-400
78.50	Closing cor. to secs. 1 & 2 in T.1 S.R.35 E., a post 4 ft. long, 4 ins. square, set firmly in the ground, marked with 6 notches on S and 5 notches on W. and 1 notch on E. edges, with S.1 on E. and S.2 on W. faces; other marks are illegible; from which A Fir 14 ins. in diam. bears N45°E.47 lks.dist. A Pine 12 " " " " S35°E.25 " " A Pine 10 " " " " S15°W.29 " " Marks illegible.	
80.00	Cor. to Secs. 35 and 36 T.1 N.,R.35 E., which is a post 4 ft. long, 4 ins. square, 24 ins. in the ground, well preserved, marked S.C.T1NR35E on N.; S36 on E and S35 on W faces with 1 notch on E. and 5 notches on W edges, from which A Tamarack 12 ins. in diam. bears N60°E 7 lks. dist., marked S.C.T.1 N.R.35E.S.36 B.T. A Tamarack 12 ins. in diam. bears S25° W.18 lks.dist., marked S.C.T1S.R.35E. B.T. A Pine, 12 ins. in diam. bears N.50°W.36 lks.dist., marked S.C.T1NR35E.S35.B.T. The first above named tree being dead, I marked instead, A Pine, 10 ins. in diam. bears N60° E. 15 lks. dist. S.C.T.1 N.R.35 E. S36 B.T. Land, badly broken. 80. chs. Soil, 2nd rate. Some grass. Good timber: Pine, Fir and Tamarack.	