

Base Line, T.1 N.R. 35 E. (S. Boundary).

| Chains | | |
|--|---|------|
| | Thence East retracing S. bdy. of sec. 36. Var. 20°45' East | |
| 15.00 | Top of ridge N. Descend. | +800 |
| 32.50 | Canon and dry branch N. | -400 |
| 40.20 | Set basalt stone 16x12x10 ins., 10 ins. in the ground in exact spot of old post cor., which is badly decayed, for $\frac{1}{4}$ sec. cor., marked S.C. $\frac{1}{4}$ on N. face, from which A Pine, 36 ins. in diam. bears S.70°E 48 lks. dist., marked S.C. $\frac{1}{4}$ S.B.T. A Pine, 14 ins. in diam. bears S35°E 112 lks. dist., marked S.C. $\frac{1}{4}$ S.B.T. | |
| | Ascend. | |
| 48.00 | Top of hill small prairie. | +400 |
| 50.00 | Canon, course N. | -200 |
| 80.40 | Cor. to Tps. 1 N R 35 and 36 E., which is a post $4\frac{1}{2}$ ft. long, 4 ins. square set firmly in the ground marked S.C.T. 1 N. on N.; S31R36E on E., and S36R35E on W. faces with 6 notches on N.E. and W. edges, from which A Spruce, 8 ins. in diam. bears N30E31 lks. dist., marked S.C.T. 1 N.R. 36E. S31 B.T. A Pine, 14 ins. in diam. bears N15°W. 37 lks. dist., marked S.C.T. 1 N.R. 35E. S36 B.T. A Pine, 12 ins. in diam. bears S.50°W. 32 lks. dist., marked S.C.T. 1 S.R. 36 E.B.T. | |
| | Land, rolling, not so rough as last mile. | |
| | Heavy timber: Pine, fir and tamarack. | |
| | Good pasture land 80.40 chains. | |
| | June 14th, 1887. | |
| General Description | | |
| This line (T.1, N.R. 35 E.) passes over or across summit of Blue Mountains through heavy timber and dense brush. The soil is not so rocky as on Western side of mt. but produces fine grass in abundance where the timber is open. The timber is generally small but very thick. | | |