

## Subdivisional lines, T. 1 N., R. 35 E.

Chains		
11.00	Summit ridge N & S.	+200
24.47	Intersect U.R. bdy. 14.63 chs. N20°E of 45th Mile cor. and set stone 18x12x6 ins., 12 ins. in the ground for closing corner to secs. 1 & 12, marked U.R.C.C. on W. face and raised stone mound over it. Pits impracticable.	
	Land, high and mountainous 24.47 chs.	
	Soil, 2nd rate. Grass fine.	
<hr/>		
	North bet. secs. 1 & 2.	
	Var. 27°20' East.	
	Descend.	
15.65	Canon & creek. Course N.W.	-1000
18.00	Leave creek bottom and ascend.	
21.50	Canon W.	- 100
25.50	Canon S.W.	- 200
	Ascend.	
39.00	Summit ridge.	+400
40.00	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ on W. face and raised mound of stone over it. Pits impracticable.	
	Descend.	
55.00	Canon S.W.	-600
	Ascend.	
80.60	Intersect Tp. line 3.65 chs. E. of corner to secs. 35 & 36, T2 N R 35 E. Set stone 8x8x8 ins., 6 ins. in the ground for closing corner to secs. 1 & 2, marked C.C. on S. face with 1 notch on E. and 5 notches on W. edges and raised mound of stone over it. Pits impracticable.	
	Land, mountainous 80.60 chs.	
	Soil, 3rd rate. Grass, good.	
	No timber.	
<hr/>		
	North bet. secs. 2 & 3.	
	Var. 19-3/4° East.	
	Ascend.	