

## Subdivisional lines, T. 1 N., R. 35 E.

Chains		
	North bet. secs. 9 & 10. Var. $17\frac{1}{4}^{\circ}$ East.	
22.00	Gulch W.	-200
40.00	Summit sharp ridge and set basalt stone 16x16x8 ins., 12 ins. in the ground for $\frac{1}{4}$ S. corner, marked $\frac{1}{4}$ S on W. face; raised mound of stone over it. Pits impracticable.	+300
52.50	Gulch, W.	-150
62.00	Summit of ridge W.	+200
77.25	Gulch W.	-200
80.00	Set stone 14 x 12 x 12 ins., 8 ins. in the ground for cor. to secs. 3, 4, 9 & 10, marked with 5 notches on S. and 3 notches on East edges; raised mound of stone over it. Pits impracticable.	
	Land, rough and mountainous 80.00 chs. Soil, 3rd rate and very rocky. Grass, good. No timber.	
	East on random bet. secs. 3 & 10. Var. $19^{\circ}$ East.	
40.00	Set temporary $\frac{1}{4}$ S. cor. and at	
80.25	Intersect E. bdy. 42 lks. N. of cor. to Secs. 2, 3, 10 & 11,	
	Thence	
	N. $89^{\circ} 42'$ West on true line. Var. $19-3/4^{\circ}$ East.	
11.50	Summit N.	+150
40.12	Set stone 20 x 14 x 12 ins., 14 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, from which A Tamarack 10 ins. in diam. bears S. $20^{\circ}$ W. 68 lks. dist. No other tree within limits; raised mound of stone over it.	
62.50	Summit N.	+300
80.25	Cor. to secs. 3, 4, 9 & 10. Land, rough and mountainous 80.25 chs. Soil, 1st rate. Grass, good. Scattering timber, pine and fir, and some underbrush, same.	
	June 22, 1887.	