

Subdivisional Lines, T. 1 N., R. 35 E.

Chains	
	<p>A Pine 12 ins. in diam. bears N.75° W. 14 lks. dist., marked R35 E. S29 B.T.</p> <p>Land, level or nearly so.</p> <p>Dense growth of underbrush. Pine, fir, spruce and tamarack 80 chs.</p> <p>Soil, 1st rate. No grass.</p>
	<p>East on random bet. secs. 28 & 33.</p> <p style="text-align: right;">Var. 19½° East.</p>
40.00	Set temporary ¼ Sec. cor. and at
80.00	Intersect E. bdy. 7 lks. S of cor. to Secs. 27, 28, 33&34.
	Thence
	S.892 57' W. on true line.
	Var. 19°40' E.
31.00	Pendleton & LaGrande Wagon Road N.W.
40.00	A Black Pine 8 ins. diam., marked ¼S on N. face for ¼ S.cor., from which
	A Pine 14 ins. in diam. bears N.65°E. 15 lks. dist., marked ¼ S.B.T.
	A Pine 10 ins. in diam. bears S.50°E. 10 lks. dist., marked ¼S. B. T.
67.00	Creek, 10 lks, course S.
71.15	Wagon Road N.W.
80.00	Cor. to secs. 28, 29, 32 & 33.
	Land, rolling. Soil, good. Timber, heavy; Pine, Spruce and Fir 80.00 chs. Underbrush, Willow, spruce and fir. Bunch grass.
	North bet. secs. 28 & 29.
	Var. 19½° East.
	Descend gradual slope.
39.80	Pendleton and La Grande Wagon Road N.W.
40.00	Set basalt stone 12 x 10 x 7 ins., 8 ins. in the ground for ¼ S. corner, marked ¼ on W. face, from which
	A Red Fir 12 ins. in diam. bears N.62°E.12 lks. dist., marked ¼ S.B.T.