

Subdivisional lines, T. 1 N., R. 35 E.

Chains	Thence	
	S.89°52' W. on true line.	
	Var. 18° East.	
18.50	Creek 20 lks. runs N.E.	-400
40.08	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ S. cor., marked $\frac{1}{4}$ on N face; raised mound of stone over it. Pits impracticable.	+200
41.50	Gulch N.E.	-50
43.00	Begin ascent.	
80.16	Cor. to secs. 16, 17, 20 and 21 on top of mountain.	+1200
	Land, mountainous 80.16 chs.	
	Timber: Pine, fir and tamarack in canons.	
	Soil, 4th rate, rocky. Grass, poor.	
North bet. Secs. 16 & 17.		
	Var. 19° East.	
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W face, from which A Pine 24 ins. in diam. bears N.62 $\frac{1}{2}$ °W 45 lks. dist., marked $\frac{1}{4}$ S.B.T. A Fir 36 ins. in diam. bears N.52°E.45 lks. dist., marked $\frac{1}{4}$ S.B.T.	
62.50	Pendleton & La Grande Wagon Road N.E.	
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 8, 9, 16 & 17, marked T1 N S 16 on N.E. R35E S16 on S.E.; S17 on S.W. and S8 on N.W. faces, with 4 notches on South and East edges, from which A Pine 20 ins. in diam. bears S35°E.55 lks. dist., marked T1NR35E S16 B.T. A Pine 16 ins. in diam. bears S87°W. 85 lks. dist., marked T1 N S17 B.T. A Pine 20 ins. in diam. bears N45°W. 75 lks. dist., marked R35E S8 B.T.	
	No other tree in limits, and raise mound of stone around post.	
	Land, rolling. Soil, 2nd rate. Timber, Scattering Pine. Grass, good.	
	June 23, 1887.	