

Subdivisional lines, T. 1 N., R. 35 E.

Chains	<p>A pine, 18 ins. in diam. bears S 76° E 138 lks. dist., marked T.1 N.R. 35 E. S32 B.T.</p> <p>No other trees in limits, raised mound of stone around post.</p> <p>Land, broken;</p> <p>Soil, 2nd rate.</p> <p>Timber, heavy pine, fir and underbrush, 80 chains.</p>
	<p>East on random bet. secs. 29 & 32.</p> <p style="text-align: right;">Var. 20½° E.</p>
40.00	Set temporary ¼ S. cor. and at
80.60	Intersect E. bdy. at cor. to secs. 28, 29, 32 & 33.
	Thence,
	West on true line.
	Var. 19½° East.
5.00	Old stage road S.W.
22.50	Same N.W.
40.30	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ S. corner marked ¼ S on N. face, from which
	A fir 16 ins. in diam. bears N. 51° W. 125 lks. dist., marked ¼ S. B. T.
	A pine 25 ins. in diam. bears S. 65° W. 76 lks. dist., marked ¼ S. B. T.
64.00	Wagon road N.
80.60	Cor. to secs. 29, 30, 31 and 32.
	Land, rough.
	Timber, pine and fir, dense undergrowth 80.60 chs.
	Soil, 2nd rate. Grass, good.
	<p>West on random bet. secs. 30 and 31.</p> <p style="text-align: right;">Var. 20½° East.</p>
40.00	Set temporary ¼ S. cor. and at
79.60	Intersect Tp. line at cor. to secs. 25 and 26, 30 and 31,
	Thence
	East on true line.
	Var. 19/° East.
36.00	Descend steep hill side.