

Subdivisions, T. 1 N., R. 35 E.

Chains	R.R. track.
2.00	Leave R.R. - ascend over broken ground.
40.15	Set a fir post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S. on N. face; from which <p style="margin-left: 40px;">A pine 22 ins. in diam. bears S. $56\frac{1}{2}^{\circ}$ W., 10 lks. dist., marked $\frac{1}{4}$ S. B. T., and A fir 14 ins. in diam. bears N. 89° E. 12 lks. dist., marked $\frac{1}{4}$ S. B. T.</p>
	Descend.
77.30	Creek 2 lks. wide, course S.W. Ascend.
80.30	The cor. to secs. 25, 26, 35 and 36. Land, mountainous, 80.30 chs. Soil, sandy loam, 3d rate. Timber, scattering pine, fir and tamarac. Undergrowth, pine, fir and tamarac. Mountainous lands 80.30 chs. <p style="text-align: center;">June 21st, 1896.</p>
	The cor. to secs. 34, 35, 2 and 3 having been washed out and the witness trees having been destroyed, in order to reestablish it, I go to the $\frac{1}{4}$ sec. cor. to secs. 34 and 3, which is a stone 6 ins. above ground marked and witnessed as described by the Surveyor General. <p style="text-align: center;">Thence, I run</p>
	East. bet. secs. 34 and 3. Ascend gradually - on blazed line.
0.70	Road, course N. and S.
3.07	U. R. Cor. bears N. 20 lks.
19.00	Summit of hill - descend.
36.75	Foot of hill - descend.
37.83	O.R. & N. R.R. - course N. and S.W.
39.57	Meacham Creek 40 lks. wide - course N.
40.00	Set fir post 3 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 34, 35, 2 and 3; marked T.1 N.S.35 on N.E.; R.35 E. S.2 on S.E.; T.1 S.S.3 on S.W. and S.34 on N.W. faces, with 2 notches on E. and 4 on W. edges,