

0.1

Subdivisions, T. 1 N., R. 35 E.

Chains

A tamarac 7 ins. in diam. bears N.43° W. 7 lks. dist.,
marked $\frac{1}{4}$ S. B. T.

This corner in point of young timber.

Although I made, and caused to be made, diligent search,
we found no trace of any former corner.

60.00 Descend steep N. point.

65.00 Enter heavy timber.

73.50 Foot of hill - 1000 ft. below last summit.

74.30 Creek 10 lks. wide - course N. 50 W.

76.00 Ascend very steep N.W. face.

77.00 Leave timber; bears N.W. and S.E.

80.00 Set a fir post, 3 ft. long, 4 ins. square, 24 ins. in the +100
ground for cor. to secs. 12, 13, 7 and 18, marked
T.1 N S.7 on N.E.; R.36 E. S18 on S.E.; R 35 E.S13 on
S.W., and S.12 on N.W. faces; with 4 notches on S. and
2 on N. edges, from which

A pine 30 ins. in diam. bears S.24° E. 315 lks. dist.,
marked T.1 N.R. 36 E. S.18 B.T.

A pine, 36 ins. in diam. bears S.28° W. 197 lks. dist.,
marked T.1 N R 35 E. S.13 B.T.

No trees within limits in secs. 12 and 7. Pits and mounds
impracticable.

Land, mountainous. Soil, sandy loam, 3rd rate.

Timber, heavy pine, fir, tamarac and spruce, 12 chs.

Scattering pine, fir, tamarac and spruce, 61 chs.

Undergrowth of pine, fir and willow 12 chs.

Mountainous lands, 80 chs.

June 25th, 1895.

The random line bet. secs. 12 and 13 intersects E. bdy. of
Tp. at 79.87 dist. and 3 lks. N. of cor. to secs. 12,
13, 7 and 18.

Thence, I run

S.89° 43' W. on true line bet. secs. 12 and 13.

Descending steep S.W. face. No timber.

4.00 Enter heavy timber - bears N.W. and S.E.

6.71 Creek 10 lks. wide, course N.W. Ascend.