

Corrections of Subdivisions, T. 1 N., R. 35 E.

<p>Chains</p>	<p>Thence, I run N.0° W. bet. secs. 34 and 35 following a well blazed line.</p> <p>40.00 A fir post, 3 ins. square, set firmly in ground, marked $\frac{1}{4}$ S on W. face, from which A pine 9 ins. in diam. bears S.16° W.39 lks. dist., marked $\frac{1}{4}$ S. B. T. A pine 11 ins. in diam. bears N. 52° E. 32 lks. dist., marked $\frac{1}{4}$ S.B.T.</p> <p>80.00 A fir post 4 ins. square set firmly in the ground correctly marked for cor. of secs. 26, 27, 34 & 35, from which A fir 13 ins. in diam. bears N.1° E. 10 lks. dist., marked T. 1 N.R. 35 E. S.26 B.T. (I made an error in the bearing of this witness tree; perhaps in copying my notes; its correct course is N.1° E. and S. 71° W. is correct.) A fir 20 ins. in diam. bears S. 53° E. 29 lks. dist., marked T.1 N.R. 35 E. S.35 B.T. A fir, 17 ins. diam. bears S.71° W. 51 lks. dist., marked T.1 N.R. 35 E. S.34 B. T., and A fir, 22 ins. diam. bears N.63° W. 32 lks. dist., marked T.1 N.R. 35 E. S.27 B.T.</p> <hr/> <p>N.0° 11' E. bet. secs. 26 and 27. Var. 20° East.</p> <p>.50 The old sec. cor. which stood 15 lks. E. of this point is destroyed; I now destroy the marks on the remaining witness trees.</p> <p>24.42 Intersect U.I.R. Bdy. at C.C. established by me. The post set by me has been taken away and replaced by the one formerly set by U.S. Dept. Surveyor, Curran & Noland, which is a tamarack post marked U.R. on the W. and C.C. on the E. in the mound raised by me, from which A pine 20 ins. in diam. bears S.60$\frac{1}{2}$° W. 86 lks. dist., marked T.1 N.R. 35 E. S.27 B.T.</p> <p>There being no other tree within limits in sec. 26, I now build a mound of stone 2$\frac{1}{2}$ ft. base, 1$\frac{1}{2}$ ft. high E. of corner.</p> <p>The former witness being erroneous, I destroy the marks thereon.</p>
---------------	--