

Corrections of Subdivisions, T. 1 N.R. 35 E.

Chains

I now return to cor. of secs. 26, 27, 35 and 34.

Thence, I run

West bet. secs. 27 and 34.

7.66 Intersect U.I.R. bdy. at point of previously established C. C. and 42 lks. S. 20° W. of C.C. by Curran & Noland for surveys within the Reservation.

I find where I set the cor. but there is no cor. now. To reestablish it, I set

A tamarack post 3 ft. long, 3 ins. square, 24 ins. in the ground for closing cor. of secs. 27 and 34, marked C.C.T.1 N.R.35 E. on E.; S.27 on N., and S.34 on S. faces, from which

A pine 10 ins. in diam. bears N. 37° E. 130 lks.dist., marked T.1 N.R.35 E. S.27 B. T., and

A pine 24 ins. in diam. bears S. 39½° E. 40 lks.dist., marked T.1 N.R.35 E. S.34 B.T.

Note: If this was 8.30 chs. as reported by the Ex., it would be out of limits with the S. bdy. of sec. 34 as well as with the E. bdy. of 27 as reported by the Ex. himself. (For explanation of this corner, see page 68. June 30th, 1897.

I now go to the cor. of secs. 35 and 36 on the S. bdy of the Tp.

Thence, I run

N.0° 1' W. bet. secs. 35 and 36.

Var. 19° East.

40.00 My former cor. A basaltic stone 20 x 10 x 10 ins., 15 ins. in the ground, marked ¼ on W. face, from which

A pine 14 ins. diam. bears S.9° E. 73 lks. dist., marked ¼ S.B.T., and

A pine 24 ins. diam. bears N.54½° W.93 lks. dist., marked ¼ S. B. T.

80.00 The post and witnesses as before reported.

N.0°1' W. bet. secs. 25 and 26.

Var. 16° East