

Corrections of Subdivisions, T. 1 N., R. 35 E.

Chains	I follow a well blazed line and find the cors. and witnesses correct as before given.
40.00	From the cor. of secs. 23, 24, 25 and 26, I run N. 89° 42' W. bet. secs. 23 and 26. Var. 18° East.
60.08	Cor. and witnesses as before described. Intersect U.I.R. bdy. at C.C. which I find as given before.
	I also examine several other lines and find them practically correct and as before reported. July 20th, 1897.
	A.M. and P.M. observations made and latitudes taken daily. (Signed) Manius Buchanan U.S. Dept. Surveyor.
	Field Notes of the supplemental survey of the Subdivisional lines of T. 1 N., R. 35 E., by Manius Buchanan under his contract No. 635, Dated April 19, 1895.
7.72	As instructed I reexamine the line bet. secs. 34 and 35, and find it correct in alignment and measurement, Therefore from cor. of secs. 26, 27, 34 and 35 Thence, I run West bet. secs. 27 and 34. Descending gradually through scattered timber. Intersect U.I.R. Bdy. line 40 lks. S. 20° W. of closing cor. to fractional secs. 27 and 24, heretofore described. Being out of limits, I set a basalt stone 19 x 11 x 8 ins., 15 ins. in the ground for closing corner to fractional secs. 27 and 34, marked C. C. on E; with one groove on S. and 5 on N. faces, raised a mound of stone 2 ft. base, 1½ ft. high on E. Pits impracticable. (For reestablishment of this corner, see Page 67)