

Resurvey of the Base Line through Range 36 East.

Chains	West on Base Line on S. boundary of sec. 34. Var. 23° E.
	Ascend about 150 ft. to
10.00	Top of ridge, course N.E.
	Descend about 200 ft. to
22.00	Bottom of gulch, course N.E.
	Ascend about 200 ft. to
36.00	Top of ridge, course N.E.
40.00	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked B L $\frac{1}{4}$ S on N. face, from which, A tamarack, 18 ins. diam., bears N.80°E., 19 lks. dist., marked $\frac{1}{4}$ S B T. A tamarack, 12 ins. diam., bears S.10°E., 52 lks. dist., marked $\frac{1}{4}$ S B T. I made careful search but could find no trace of the old $\frac{1}{4}$ sec. cor.
54.00	Bottom of gulch, about 150 ft. below ridge, course N.E.
80.00	Set a post 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 33 and 34 marked B L T 1 N R 36 E on N., S 34 on E. and S 33 on W. faces, with 3 notches on E. and W. faces, from which, A fir, 20 ins. diam., bears N.75°E., 62 lks. dist., marked T 1 N R 36 E S 34 B T. No other tree within limits, and raised mound of stone alongside. I made careful search but could find no trace of old sec. cor. Land, mountainous. Soil, stony, 3rd rate. Timber, scattering pine, fir and tamarack.
	West on Base Line on S. boundary of sec. 33. Var. 20 $\frac{1}{4}$ °E.
4.00	Top of ridge, course S.
12.00	Bottom of gulch about 100 ft. below ridge, course S.