

North boundary of T. 1 N., R. 36 E.

Chains	
	<p>stone alongside.</p> <p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Heavily timbered with fir, tamarack, pine on E. 20 chs.</p>
	<p>N.89°39'W. on a true line between secs. 2 and 35.</p> <p style="text-align: center;">Var. 22½°E.</p> <p>Descend about 1000ft. to</p>
35.00	Bottom of gulch, course S.W.
40.00	Set a basalt stone, 18x14x12 ins., 12 ins. in the ground, for ¼ sec. cor. marked ¼ on N. face, and raised a mound of stone alongside.
49.00	Top of ridge, about 800 ft. above gulch, course S.W. Descend about 1000 ft. to
80.00	Set a basalt stone, 15x12x10 ins., 10 ins. in the ground, for cor. to secs. 2, 3, 34 and 35, marked with 2 notches on E. and 4 notches on W. edges, and raised a mound of stone alongside.
	<p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Good bunch grass. No timber.</p>
	<p>N.89°39'W. on a true line between secs. 3 and 34.</p> <p style="text-align: center;">Var. 21° E.</p> <p>Descend about 150 ft. to</p>
6.00	Bottom of gulch, course S.W.
39.50	A gulch, course S. about 500 ft. below last gulch.
40.00	Set a basalt stone, 16x16x8 ins., 11 ins. in the ground, for ¼ sec. cor. marked ¼ on N. face, from which
	<p>A pine, 9 ins. diam., bears N.4°W., 18 lks. dist., marked ¼ S B T.</p> <p>A pine, 14 ins. diam., bears S.85°W., 15 lks. dist., marked ¼ S B T.</p>
	Ascend about 1000 ft. to
77.50	Top of ridge, course S.W.