

Subdivisions of T. 1 N., R. 36 E.

| | |
|--------|---|
| Chains | <p>North between secs. 23 and 24.</p> <p style="text-align: center;">Var. 19°E.</p> <p>Descend about 300 ft. to</p> <p>25.00 Bottom of gulch, course S.E.</p> <p>40.00 Set a basalt stone, 16x8x6 ins., 11 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, from which,</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., bears S.45°E., 145 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p style="padding-left: 40px;">A pine, 40 ins. diam., bears S.80°W., 110 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>80.00 A point about 900 ft. above gulch. Set a basalt stone, 13x12x4 ins., 9 ins. in the ground, for cor. to secs. 13, 14, 23 and 24, marked with 3 notches on S. and 1 notch on E. edges, and raised a mound of stone alongside.</p> <p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Timber, scattering pine and fir with dense undergrowth of buck brush.</p> |
| | <p>East on a random line between secs. 13 and 24.</p> <p style="text-align: center;">Var. 23$\frac{1}{2}$°E.</p> <p>Ascend about 75 ft. to</p> <p>5.00 Top of ridge, course S.E.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>41.50 Bottom of gulch, about 300 ft. below ridge, course S.E.</p> <p>62.50 Top of ridge about 400 ft. above gulch, course S.E.</p> <p>Descend about 300 ft. to</p> <p>80.16 Intersect 10 lks. S. of the cor. to secs. 13, 24, 18 and 19, which is a post, 4 ins. square, marked T 1 S S 18 on N.E., R 37 E S 19 on S.E., R 36 E S 24 on S.W., and S 13 on N.W. faces, with 3 notches on N. and S. edges, from which,</p> <p style="padding-left: 40px;">A pine, 24 ins. diam., bears N.50°E., 119 lks. dist., marked T 1 N R 37 E S 18 B T.</p> |