

## Subdivisions of T. 1 N., R. 36 E.

Chains	Var. 23°E.
	Ascend along hillside.
5.00	Top of ridge about 75 ft. above cor., course N.E. Enter timber.
20.00	Bottom of gulch about 400 ft. below ridge, course E.
29.50	Top of ridge about 100 ft. above gulch, course E.
40.00	Foot of hill about 200 ft. below ridge, N.W. Set a post, 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on W. face, from which, A fir, 4 ins. diam., bears S.68°E., 21 lks. dist., marked $\frac{1}{4}$ S B T. A fir, 3 ins. diam., bears N.15°W., 10 lks. dist., marked $\frac{1}{4}$ S B T.
40.25	Dry bed of Meacham crk. 50 lks. wide, course N.W.
49.50	Intersect graded track of the Baker City Branch of the O. R. and N. Cos. Railway line.
50.50	Wagon road, course N.W.
57.50	North fork of Meacham creek, 50 lks. wide, runs W.
61.00	Grasty's house bears W. 2.50 chs. dist.
80.00	Set a basalt stone, 18x6x5 ins., 12 ins. in the ground, for cor. to secs. 26, 27, 34 and 35 marked with 1 notch on S. and 2 notches on E. edges, from which, A fir, 12 ins. diam., bears S.30°E., 90 lks. dist., marked T 1 N R 36 E S 35 B T. A fir, 8 ins. diam., bears S.40°W., 129 lks. dist., marked T 1 N R 36 E S 34 B T. A pine, 28 ins. diam., bears N. 55°W., 206 lks. dist., marked T 1 N R 36 E S 27 B T. No other tree within limits, and raised a mound of stone alongside.
	Land, mountainous.
	Soil, sandy loam and stony, 2nd and 3rd rate.
	Heavily timbered with fir, pine and tamarack on N. 75.00 chs.