

Subdivisions of T.1 N., R. 36 E.

Chains	mound of stone alongside.
80.36	The cor. to secs. 28, 29, 32 and 33. Land, mountainous. Soil, stony, 3rd rate. Timber, scattering fir, pine and tamarack with dense undergrowth of mountain laurel, wild cherry, and alder. September 18, 1882.
	North between secs. 28 and 29. Var. 20°E. Descend about 100 ft. to 20.00 Bottom of gulch, course W. 30.00 Top of ridge, about 125 ft. above gulch, course N.W. 40.00 Set a basalt stone, 12x12x4 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone alongside. 55.00 Bottom of gulch about 150 ft. below ridge, course N.E. 65.00 Top of ridge about 150 ft. above gulch, course N.E. 80.00 Set a basalt stone, 18x9x6 ins., 12 ins. in the ground, for cor. to secs. 20, 21, 28 and 29, marked with 2 notches on S. and 4 notches on E. edges, from which, A fir, 5 ins. diam., bears S.25°E., 115 lks. dist., marked T 1 N R 36 E S 28 B T. A fir, 6 ins. diam., bears S.25°W., 131 lks. dist., marked T 1 N R 36 E S 29 B T. No other tree within limits, and raised a mound of stone alongside. Land, mountainous. Soil, 2nd rate. Timber, scattering fir and pine with dense undergrowth of mountain laurel and wild cherry.
	East on a random line between secs. 21 and 28. Var. 22 $\frac{1}{4}$ °E. 14.50 Top of ridge about 100 ft. above cor., course N.E. 22.00 Bottom of gulch about 100 ft. below ridge, course N.E.