

Subdivisions of T. 1 N., R. 36 E.

Chains 40.16	Set a basalt stone, 16x12x4 ins., 11 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.
80.32	The cor. to secs. 29, 30, 31 and 32. Land, mountainous. Soil, stony, 3rd rate. Timber, scattering fir and pine with dense undergrowth of buck brush.
	West on a random line between secs. 30 and 31. Var. $22\frac{1}{2}^{\circ}$ E. Through timber.
.40	Wagon road, course N.W.
4.00	Meacham creek, 50 lks. wide, course S.W.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
64.00	Dry bed of Meacham creek, 75 lks. wide, course N.E.
65.50	Wagon road, course N.E.
90.84	Intersect W. boundary, 10 lks. S. of the cor. to secs. 30, 31, 25 and 36, which is a post, the marks have been nearly obliterated by fire and the bearing trees have been cut down, but I found the stumps of same agreeing with notes. I re-establish the cor. as follows: Set a basalt stone, 12x10x6 ins., 8 ins. in the ground, marked with 1 notch on S. and 5 notches on N. edges, from which, A fir, 7 ins. diam., bears N.25°E., 150 lks. dist., marked T 1 N R 36 E S 30 B T. A fir, 28 ins. diam., bears S.85°E., 69 lks. dist., marked T 1 N R 36 E S 31 B T. A fir, 10 ins. diam., bears S.35°W., 46 lks. dist., marked T 1 N R. 35 E S 36 B T. A fir, 12 ins. diam., bears N.10°W., 140 lks. dist., marked T 1 N R 35 E S 25 B T. Thence I run S.89°56'E. on a true line between secs. 30 and 31.