

Subdivisions of T. 1 N., R. 36 E.

Chains	<p>No other tree within limits. and raised a mound of stone alongside.</p> <p>90.57 The cor. to secs. 19, 20, 29 and 30. Land, mountainous. Soil, 2nd rate. Timber, scattering pine and fir and tamarack, with dense undergrowth of mountain laurel.</p> <p style="text-align: right;">September 21, 1882.</p>	
	<p>North between secs. 19 and 20.</p> <p style="text-align: right;">Var. 19°E.</p> <p>Through timber.</p> <p>40.00 Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, from which,</p> <p style="padding-left: 40px;">A pine, 8 ins. diam., bears N.45°E., 4 lks. dist., marked $\frac{1}{4}$ S. B. T.</p> <p style="padding-left: 40px;">A cherry, 3 ins. diam., bears S.35°W., 10 lks. dist., marked $\frac{1}{4}$ S. B. T.</p> <p>80.00 Set a post, 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to secs. 17, 18, 19 and 20 marked T 1 N S 17 on N.E., R 36 E S 20 on S.E., S 19 on S.W., and S 18 on N.W. faces with 3 notches on S. and 5 notches on E. edges, from which,</p> <p style="padding-left: 40px;">A pine, 6 ins. diam., bears N.45°E., 11 lks. dist., marked T 1 N R 36 E S 17 B T.</p> <p style="padding-left: 40px;">A pine, 28 ins. diam., bears S.60°E., 25 lks. dist., marked T 1 N R 36 E S 20 B T.</p> <p style="padding-left: 40px;">A fir, 4 ins. diam., bears S.25°W., 22 lks. dist., marked T 1 N R 36 E S 19 B T.</p> <p style="padding-left: 40px;">A fir, 7 ins. diam., bears N.35°W., 89 lks. dist., marked T 1 N R 36 E S 18 B T.</p> <p>Land, mountainous. Soil, sandy loam, 2nd rate. Timber, scattering pine, fir and tamarack, with dense undergrowth of pine, fir, tamarack, wild cherry and buck brush.</p>	