

Base Line of T. 1 N., R. 37 E.

Chains	<p>A white fir, 6 ins. in diam., bears N.20°W., 38 lks. A white fir, 6 ins. in diam., bears N.75°E., 26 lks. Var. 21°45'East.</p> <p>Surface and timber as before.</p>	
	Thence East on South boundary of sec. 34.	
19.00	Bottom of ravine and spring branch, 10 lks. wide, runs N.	-300
40.00	Set qr. sec. post, from which, A red fir, 10 ins. in diam., bears S.20°W., 79 lks. dist. A tamarack, 16 ins. in diam., bears S.15°E., 65 lks. dist.	+300
45.00	Commence to descend into deep canyon.	
80.00	Set post corner to secs. 34 and 35, from which, A hemlock, 8 ins. in diam., bears N.35°E., 25 lks. A red fir, 12 ins. in diam., bears N.30°W., 35 lks. Var. 20°East.	-1000
	Thence East on South boundary of sec. 35.	
13.00	Bottom of canyon and intersect creek, 20 lks. wide, runs North. August 12, 1863.	-800
40.00	Set qr. sec. post on side of canyon, from which, A red fir, 8 ins. in diam., bears N.30 lks. dist. A tamarack, 10 ins. in diam., bears S.40°E., 25 lks.	+800
80.00	Set post corner to secs. 35 and 36 on side of ridge, from which, A hemlock, 16 ins. in diam., bears N.E. 65 lks. dist. A tamarack, 18 ins. in diam. bears N.20°W., 52 lks." Var. 19°30'East.	
	Thence East on South boundary of sec. 36.	
20.00	Top of ridge, N. and South.	+1000
40.00	Set qr. sec. post in bed of branch, 10 lks. wide, running South, from which,	-1000