

## Base Line of T. 1 N., R. 37 E.

Chains   80.00	<p>A spruce, 7 ins. in diam., bears S.65°E., 52 lks.  A hemlock, 16 ins. in diam., bears S.80°E., 64 lks.  Set post corner to secs. 31 and 36, Townships No. 1  North, Ranges 37 and 38 East, from which,  A spruce, 5 ins. in diam., bears N.60°W., 61 lks.  A spruce, 5 ins. in diam., bears N.20°E., 58 lks.  A spruce, 12 ins. in diam., bears S.45°W., 20 lks.  Var. 17°10' East.</p>	+400
<p>Exterior of T. 1 N., R. 38 E.  Surveyed by Jacob C. Cooper under contract No. 397.  Dated July 1, 1881.  (West Boundary)</p>		
<p>From Base Line cor. to Tps. 1 N., Rs. 37 and 38 E., which  is a post decayed and rotten. I set a new post marked  T 1 N on N., R 38 E S 31 on E., R 37 E S 36 on W., and  with 6 notches on N. E. and W. faces.  A spruce, 5 ins. diam., bears N.60°W., 61 lks. dist.,  marked T 1 N R 37 E S 36 B T.  A spruce, 5 ins. diam., bears N.20°E., 58 lks. dist.,  marked T 1 N R 38 E S 31 B T.  A spruce, 12 ins. diam., bears S.45°W., 20 lks. dist.,  marked T 1 S R 37 E S 1 B T.  I run  N. between secs. 31 and 36.  Var. 18°15'E.</p>		
5.00	Ascend through dense buck brush and young pine timber. Glade.	
8.00	Enter timber. Descend.	
28.00	Spring branch, course W. Ascend.	
31.00	Glade.	
40.00	<p>Set post 3½ ft. long, 3 ins. square, 16 ins. in the  ground, for ¼ sec. cor., marked ¼ S on E. and W. faces,  on S. hillside in sage brush 200 ft. above bottom of ravine.  A fir, 16 ins. diam., bears S.8°E., 32 lks. dist.,  marked ¼ S B T.  Var. 18°30'E.</p>	