

## West Boundary of T. 1 N., R. 38 E.

Chains	Top of ridge, course N. and S.
50.00	
74.00	Descend gradually along barren side of mountain sloping E.
80.00	Set post $4\frac{1}{2}$ ft. long, 4 ins. square, 2 ft. in the ground on E. side of ridge, 60 ft. below the summit in small cherry thicket near Western point of timber for cor. to secs. 25, 30, 31 and 36, marked T 1 N S 30 on N.E., R 38 E S 31 on S.E., R 37 E S 36 on S.W. and S 25 on the N.W. faces, with 1 notch on the S. and 5 notches on the N. edges.
	A fir, 30 ins. diam., bears N.56°E., 130 lks. dist. marked T 1 N R 38 E S 30 B T.
	A fir, 30 ins. diam., bears S.82°E., 104 lks. dist., marked T 1 N R 37 E S 31 B T.
	Land, high mountainous and broken.
	Soil, rocky, 4th rate.
	Timber, pine, fir and tamarack.
	September 19, 1881.
	North between secs. 25 and 30.
	Var. 16°45'E.
2.00	Brink of gravelly slide sloping E.
9.66	A scraggy fir tree, 20 ins. diam., on point of ridge, course E. and W. The point of this ridge brings us to the verge of a succession of steep rocky canyons, course E. Chaining impracticable. Therefore, I blazed said fir tree distinctly on the N. side for flag I sighted a small fir tree on high peak ahead or N. and go round to said small fir tree and run a base of 14.50 chs., which I gave an angle of 7° from blazed fir tree on the S. making the distance 118.11 chs. where I erected a mound of stone $3\frac{1}{2}$ ft. at base, 18 ins. high, 4000 ft. above Grand Ronde valley.
	A fir, 8 ins. diam., bears N.W. 320 lks. dist. marked T 1 N R 37 E S 24 W C B T.