

West Boundary of T. 1 N., R. 38 E.

Chains	
	<p>cor. marked $\frac{1}{4}$ S on the E. and W. faces.</p> <p>A fir, 18 ins. diam., bears N.13°W., 20 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A willow, 4 ins. diam., bears N.63°E., 32 lks. dist., marked $\frac{1}{4}$ S B T.</p>
43.00	A brook, course E.
44.00	Cross point at bottom of ravine. Ascend through pine timber.
47.00	Abrupt ascent; enter glade.
51.00	Through scattering pine timber. Dense buck brush, scattering timber.
74.00	Descend abruptly.
80.00	<p>Set post $4\frac{1}{2}$ ft. long, 4 ins. square, 2 ft. in the ground on N. side of ridge, 150 ft. below the summit, 250 ft. above the bottom of ravine for cor. to secs. 7, 12, 13 and 18, marked T 1 N S 7 on N.E., R 38 E S 18 on S.E., R 37 E S 13 on S.W. and S 12 on the N.W. faces with 4 notches on the S. and 2 notches on the N. edges.</p> <p>A fir, $2\frac{1}{2}$ ins. diam., bears N.18°E., 20 lks. dist., marked T 1 N R 38 E S 7 B T.</p> <p>A fir, 6 ins. diam., bears S.70°E., 18 lks. dist., marked T 1 N R 38 E S 18 B T.</p> <p>A fir, 7 ins. diam., bears S.53°W., 9 lks. dist., marked T 1 N R 37 E S 13 B T.</p> <p>A fir, 7 ins. diam., bears N.69°W., 27 lks. dist., marked T 1 N R 37 E S 12 B T.</p> <p>Land, mountainous, rough and broken. Soil, rocky, 4th rate. Timber, fir and pine.</p>
	<p>North between secs. 7 and 12. Var. 20°E.</p> <p>Descend abruptly through fir timber and dense underbrush.</p>
8.00	Bottom of ravine. Ascend.
31.00	Summit of ridge, course W. Var. 28°50'E.