

West Boundary of T. 1 N., R. 38 E.

Chains	
40.00	<p>Descend through heavy forest of timber. Dense underbrush.</p> <p>Set post 3 ft. long, 3 ins. square, 18 ins. in the ground, on steep N. hillside in fir timber, and dense dense undergrowth for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on the E. and W. faces.</p> <p>A fir, 13 ins. diam., bears S.40°W., 13 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A spruce, 8 ins. diam., bears S.38°E., 34 lks. dist., marked $\frac{1}{4}$ S B T.</p>
42.75	<p>Spring branch, course E.</p> <p>Ascend through heavy timber and undergrowth.</p>
52.50	<p>Along the mountain side facing E.</p>
68.25	<p>Descend through heavy forest of timber and dense underbrush.</p>
80.00	<p>Set post 4$\frac{1}{2}$ ft. long, 4 ins. square, 2 ft. in the ground, on E. side of mountain, 600 ft. above valley lying E. for cor. to secs. 1, 6, 7 and 12 marked T 1 N S 6 on N.E., R 38 E S 7 on S.E., R 37 E S 12 on S.W., and S 1 on the N.W. faces with 5 notches on the S. and 1 notch on the N. edges.</p> <p>A fir, 10 ins. diam., bears S.10°E., 98 lks. dist., marked T 1 N R 38 E S 7 B T.</p> <p>A pine, 36 ins. diam., bears N.27°E., 144 lks. dist., marked T 1 N R 38 E S 6 B T.</p> <p>Land, rough, mountainous and broken.</p> <p>Soil, rocky, 3rd rate.</p> <p>Timber, tamarack and fir.</p>
	<p>North between secs. 1 and 6.</p> <p>Var. 20°E.</p>
	<p>Descend gradually along mountain side sloping E.</p>
4.00	<p>Cross a small ravine, course E.</p>
10.00	<p>Spring branch, course E.</p>
24.00	<p>Windfall. Dense undergrowth.</p>
40.00	<p>Set post 3$\frac{1}{2}$ ft. long, 3 ins. square, 18 ins. in the</p>