

West. Boundary of T 1 N., R. 38 E.

Chains	<p>ground on E. side of mountain sloping E. 100 ft. above valley for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on E. and W. faces.</p> <p>A fir, 18 ins. diam., bears S.75°E., 18 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p style="text-align: center;">Var. 13°E.</p> <p>79.00 A spring.</p> <p>80.00 Set post 5 ft. long, 6 ins. square, 2 ft. in the ground, in heavy fir timber and dense undergrowth, sloping E. for cor. to Tps. 1 and 2 N., Rs. 37 and 38 E. marked T 2 N S 31 on N.E., R 38 E S 6 on S.E., T 1 N S 1 on S.W., and R 37 E S 36 on N.W. with 6 notches on each edge.</p> <p>A fir, 14 ins. diam., bears S.47°E., 43 lks. dist., marked T 1 N R 38 E S 6 B T.</p> <p>A fir, 9 ins. diam., bears N.20°E., 13 lks. dist., marked T 2 N R 38 E S 31 B T.</p> <p>A fir, 10 ins. diam., bears N.19°W., 32 lks. dist., marked T 2 N R 37 E S 36 B T.</p> <p>A fir, 10 ins. diam., bears S.36°W., 65 lks. dist., marked T 1 N R 37 E S 1 B T.</p> <p>Land, rolling and mountainous.</p> <p>Soil, gravelly, 2nd rate.</p> <p>Timber, fir and tamarack.</p> <p style="text-align: right;">September 22, 1881.</p>
	<p style="text-align: center;">General Description</p> <p>This line runs along the peaks extending N. from Mount Neabo overlooking Grand Ronde valley, and is rough in the extreme. All of the Southern and Eastern portion of this Tp. has been subdivided. It is covered with heavy pine, tamarack and fir timber of value. The Tp. is well watered.</p>