

South Boundary of T. 2 N., R. 37 E.

Chains	
	<p>A spruce, 18 ins. diam., bears N.68°E., 13 lks. dist., marked T 2 R 37 E S 32 B T.</p> <p>A fir, 15 ins. diam., bears N.46°W., 26 lks. dist., marked T 2 N R 37 E S 31 B T.</p> <p>A spruce, 15 ins. diam., bears S.60°E., 21 lks. dist., marked T 1 N R 37 E S 5 B T.</p> <p>A spruce, 18 ins. diam., bears S.28°W., 24 lks. dist., marked T 1 N R 37 E S 6 B T.</p> <p>Land, mountainous and broken.</p> <p>Soil, rocky, 4th rate.</p> <p>Timber, fir, spruce and pine.</p>
	<p>N.89°58'W. on a true line between secs. 6 and 31. Var. 22°</p> <p>Descend.</p>
12.00	Bottom of ravine.
	Ascend.
40.00	<p>Set post, 3½ ft. long, 3 ins. square, 18 ins. in ground, marked ¼ S on N. and S. faces for ¼ sec. cor. on Northeast slope near W. margin of alder thicket in heavy timber.</p> <p>A fir, 46 ins. diam., bears N.40°E., 6 lks. dist., marked ¼ S B T.</p> <p>A fir, 15 ins. diam., bears S.74°W., 50 lks. dist., marked ¼ S B T.</p>
68.00	Summit of ridge, course N. and S.
	Descend.
74.00	Bottom of ravine, course North.
	Ascend.
84.00	Barren table land.
97.00	Enter timber, gradual descent.
100.58	<p>Township cor. to Tps. 1 and 2 N., Rs. 36 and 37 E. Land, mountainous and broken.</p> <p>Timber, fir, tamarack and spruce.</p> <p>Soil, rocky, 4th rate.</p>
	September 28, 1881.