

Resurvey of Base Line through Range 37 East

Chains

Land, mountainous.

Soil, 2nd and 3rd rate.

Heavily timbered with fir, tamarack and pine.

August 29, 1882.

General Description

This line runs along the North slope of the Blue Mountains. The Townships on each side are rough and broken but contain large groves of fir, tamarack and pine timber of fair quality and some streams of pure, clear water.

Subdivisions of T. 1 N., R. 37 E.
Surveyed by Herman D. Gradon under contract No. 452.
Dated June 16, 1882.

Preliminary to subdividing this township I ran North on a blank line on the East boundary of sec. 36 and at 40.00 chs. I found the $\frac{1}{4}$ sec. cor., and at 80.08 chs. I found the sec. cor. as I have just re-run the S. boundary of sec. 36. I do not retrace same. My compass will, therefore, run the same line as the exterior boundaries and the chaining practically agrees. Survey commenced August 30, 1882, with a Burts improved solar compass.

I commence at the cor. to secs. 35 and 36 on the Base Line, which is a basalt stone, 20x12x8 ins., marked B L with 1 notch on E. and 5 notches on W. edges, from which,

A fir, 6 ins. diam., bears N.7°E., 49 lks. dist.,
marked T 1 N R 37 E S 36 B T.

A fir, 22 ins. diam., bears S.85°W., 21 lks. dist.,
marked T 1 S R 37 E S 2 B T.

A fir, 24 ins. diam., bears N.45°W., 51 lks. dist.,
marked T 1 N R 37 E S 35 B T.

Thence I run

North between secs. 35 and 36.

Var. 19°E.

Ascend about 100 ft. to