

Subdivisions of T. 1 N., R. 37 E.

Chains	<p>A pine, 4 ins. diam., bears S.25°E., 13 lks. dist., marked T 1 N R 37 E S 25 B T.</p> <p>A fir, 5 ins. diam., bears S.25°W., 11 lks. dist., marked T 1 N R 37 E S 26 B T.</p> <p>A pine, 12 ins. diam., bears N.65°W., 15 lks. dist., marked T 1 N R 37 E S 23 B T.</p> <p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Heavily timbered with fir, pine and tamarack.</p>
40.00	<p>East on a true line between secs. 24 and 25.</p> <p style="text-align: center;">Var. 20$\frac{1}{4}$°E.</p> <p>Through timber.</p> <p>Set a basalt stone, 12x10x8 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone alongside.</p> <p>As the cor. to secs. 24, 25, 19 and 30 on the E. boundary of this township has never been established on account of the land being so rough that is is unsurveyable. I discontinue my line at this point.</p> <p>Land, mountainous.</p> <p>Soil, stony, 3rd rate.</p> <p>Timber, scattering fir, pine and tamarack with dense undergrowth of mountain laurel.</p>
40.00	<p>North between secs. 23 and 24.</p> <p style="text-align: center;">Var. 20$\frac{1}{4}$°E.</p> <p>Through timber.</p> <p>Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W. face, from which,</p> <p style="padding-left: 40px;">A fir, 28 ins. diam., bears S.80°E., 9 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p style="padding-left: 40px;">A fir, 3 ins. diam., bears N.75°W., 16 lks. dist., marked $\frac{1}{4}$ S B T.</p>