

Subdivisions of T. 1 N., R. 37 E.

| Chains | |
|--------|---|
| | <p>A fir, 8 ins. diam., bears S.50°W., 30 lks. dist., marked T 1 N R 37 E S 22 B T.</p> <p>A fir, 8 ins. diam., bears N.30°W., 18 lks. dist., marked T 1 N R 37 E S 15 B T.</p> <p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Timber, scattering fir, pine and tamarack, with dense undergrowth of mountain laurel.</p> |
| | <p>East on a random line between secs. 14 and 23.</p> <p style="text-align: center;">Var. 20½°E.</p> <p>39.75 A brook, 3 lks. wide, runs S.</p> <p>40.00 Set temporary ¼ sec. cor.</p> <p>80.30 Intersect 40 lks. N. of the cor. to secs. 13, 14, 23 and 24.</p> <p>Thence I run</p> <p>N.89°45'W. on a true line between secs. 14 and 23.</p> <p>40.15 Set a basalt stone, 16x12x4 ins., 11 ins in the ground, for ¼ sec. cor., marked ¼ on W. face, from which</p> <p>A fir, 14 ins. diam., bears N.20°E., 42 lks. dist., marked ¼ S B T.</p> <p>A fir, 20 ins. diam., bears S.45°E., 10 lks. dist., marked ¼ S B T.</p> <p>80.30 The cor. to secs. 14, 15, 22 and 23.</p> <p>Land, mountainous.</p> <p>Soil, sandy loam, 2nd rate.</p> <p>Heavily timbered with fir, tamarack and pine.</p> <p>Dense undergrowth of mountain laurel.</p> |
| | <p>North between secs. 14 and 15.</p> <p style="text-align: center;">Var. 20½°E.</p> <p>Over mountainous land.</p> <p>40.00 Set a basalt stone, 14x10x6 ins., 9 ins. in the ground, for ¼ sec. cor., marked ¼ on W. face, and raised a mound of stone alongside.</p> |