

Subdivisions of T. 1 N., R. 37 E.

Chains	<p>East on a random line between secs. 22 and 27.</p> <p style="text-align: center;">Var. 20°E.</p> <p>Ascend mountain.</p>
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.82	<p>A point about 1500 ft. above last sec. cor. Intersect</p> <p style="text-align: center;">35 lks. N. of the cor. to secs. 22, 23, 26 and 27.</p> <p>Thence I run</p> <p style="text-align: center;">N. 89°45'W. on a true line between secs. 22 and 27.</p>
39.96	<p>Set a post 3 ft. long, 3 ins. square, 24 ins. in the</p> <p style="text-align: center;">ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on N. face, and</p> <p style="text-align: center;">raised a mound of stone around post.</p>
79.82	<p>The cor. to secs. 21, 22, 27 and 28.</p> <p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Scattering fir and pine timber.</p> <p>Dense undergrowth of mountain-laurel.</p>
	<p>North between secs. 21 and 22.</p> <p style="text-align: center;">Var. 20°E.</p>
15.00	Dry bed of creek, course W.
40.00	<p>Set a basalt stone, 14x10x4 ins., 9 ins. in the ground,</p> <p style="text-align: center;">for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, from which,</p> <p style="text-align: center;">A fir, 24 ins. diam., bears N.85°W., 100 lks. dist.,</p> <p style="text-align: center;">marked $\frac{1}{4}$ S B T.</p> <p style="text-align: center;">No other tree within limits.</p> <p style="text-align: center;">and raised a mound of stone alongside.</p>
74.50	<p>Summit of ridge, about 1200 ft. above creek bed, course</p> <p style="text-align: center;">N.W.</p>
80.00	<p>Set a post 4 ft. long, 4 ins. square, 24 ins. in the</p> <p style="text-align: center;">ground, for cor. to secs. 15, 16, 21 and 22 marked</p> <p style="text-align: center;">T 1 N S 15 on N.E., R 37 E S 22 on S.E., S 21 on S.W.</p> <p style="text-align: center;">and S 16 on N.W. faces, with 3 notches on S. and E.</p> <p style="text-align: center;">edges, from which,</p> <p style="text-align: center;">A fir, 12 ins. diam., bears N.37°E., 15 lks. dist.,</p> <p style="text-align: center;">marked T 1 N R 37 E S 15 B T.</p>