

I.
 Between Ranges 29 & 30 E., Township 1, S., W.M.
 As surveyed by Geo. Williams and Geo. S. Pershin, Deputy Surveyors
 Under their Contract No. 154
 Dated June 6th, 1871

Chains		Feet
	From the Cor. of Tps. 1 & 29, Rs. 29 & 30 E.	
	I run	
	N. on the E. Bdy. of Sec. 36	
	Var. 20° 21' E.	
26.00	On spur brs. E.	+140
38.50	A ravine brs. S.E.	-140
40.00	Set a stone, 16 x 8 x 6 on S.W. hillside for $\frac{1}{4}$ Sec. Cor.	+20
	Var. 20° 56' E.	
65.00	Top of hill	+220
80.00	Set a stone, 24 x 7 x 5 for Cor. to Secs. 25, 36, 30 & 31.	-10
	Land; high and broken, 2nd and 3rd rate.	
	<hr/>	
	N. on the E. Bdy. of Sec. 25	
	Var. 21° 57' E.	
32.00	Foot of hill, brs. N.E. & S.W.	-220
34.00	Foot of hill on N. side of canyon, brs. N.E. & S.W.	
40.00	Set a stone, 20 x 7 x 5 on S.E. hillside for $\frac{1}{4}$ Sec. Cor.	+40
	Var. 18° 42' E.	
80.00	Set a stone, 24 x 7 x 6 on top of hill for Cor. to Secs.	+240
	24, 25, 19 & 30.	
	Land; high and broken, 2nd & 3rd rate, part worthless.	
	<hr/>	
	N. on the E. Bdy. of Sec. 24	
	Var. 21° 00' E.	
31.00	A ravine brs. W.	-150
40.00	Set a stone, 21 x 8 x 6 on S. hillside for $\frac{1}{4}$ Sec. Cor.	+60
	Var. 19° 20' E.	
57.00	Top of hill	+80
80.00	Set a stone, 22 x 7 x 6 for Cor. to Secs. 13, 24, 18 & 19	
	Land; high and broken, 2nd & 3rd rate, part worthless.	
	<hr/>	
	N. on the E. Bdy. of Sec. 13	
	Var. 20° 27' E.	
12.00	Begin to descend	
40.00	Set a stone, 24 x 8 x 5 on E. hillside for $\frac{1}{4}$ Sec. Cor.	-80
	Var. 18° 45' E.	