

Township 1 S., R. 30 E., W.M.

Chains		Feet
	Var. 21° 48' E.	
40.00	Set a stone, 16 x 7 x 6 for $\frac{1}{4}$ Sec. Cor.	-10
	Var. 22° 16' E.	
80.00	Set a stone, 16 x 8 x 6 for Cor. to Secs. 12, 13, 7 & 18. Land; gently undulating, good 2nd rate.	+20
N. on the E. Bdy. of Sec. 12.		
	Var. 22° 00' E.	
36.00	Road from Butter Creek to Burch Creek, brs. N.W. & S.E.	-10
40.00	Set a stone, 17 x 6 x 6 for $\frac{1}{4}$ Sec. Cor.	-10
	Var. 22° 28' E.	
76.00	A ravine brs. N.W.	-60
80.00	Set a stone, 24 x 6 x 4 on W. hillside for Cor. to Secs. 1, 12, 6 & 7. Land; rolling, good 2nd rate.	+20
Note:		
All the stones that I have used, to mark corners, are of the same kind, a ferruginous basalt of reddish brown color and very hard.		
N. on the E. Bdy. of Sec. 1.		
	Var. 22° 28' E.	
40.00	Set a stone, 20 x 7 x 6 on N.W. hillside for $\frac{1}{4}$ Sec. Cor.	-40
	Var. 21° 18' E.	
58.25	Foot of hill brs. N.E. & S.W. A canyon brs. N.E.	-50
62.00	A cross canyon	
78.28	To a point on the Base Line, 12 chs. and 86 lks. W. of post in mound corner to Sec. 35 and 36, T.1 N., R.30 E., W.M. Set a stone, 24 x 6 x 5 at point of intersection for Cor. to Tps. 1, S., Rs. 30 & 31 E., raised a mound of stone as per instructions. Land; rolling, 2nd rate.	
	Var. 20° 15' E.	
	Oct. 25, 1871	